


## 150.1165 | Floor Mounted Tub Filler With Hand Held Shower





## **SPECIFICATIONS:**

- Solid Brass construction includes valve
- Floor Mount Installation
- Hand shower flow rate = 1.8 GPM @ 60 PSI w/ back flow prevention
- Diverter knob controls water flow between spout and hand held
- 7.0 GPM Spout flow rate
- With 360° Swivel Spout

## STANDARDS:

• ASME A112.18.1 / CSA B125.1

Legislation Compliance



ZeroDrip Technology



## **Technical Diagram**

